

Wall Systems Compared

		Liteblok™ 38	2 x 6 Wood Frame
R-Value	Austin, TX	22	19
		(cost/ sq ft of wall)	(cost/ sq ft of wall)
Erect Wall	<i>Materials</i>	\$7.00	\$4.00
	<i>Labor</i>	\$1.00	\$8.00
	Subtotal: Erect Wall	\$8.00	\$12.00
Finish Wall	<i>Materials</i>	\$2.00	\$4.00
	Interior Paint/ Exterior Stucco <i>Labor</i>	\$2.00	\$3.00
	Subtotal: Finishing	\$4.00	\$7.00
Total: Finished Walls		\$12.00	\$19.00

Notes: Cost estimate excludes freight. 2x6 example consists of sheathing, sheetrock, fiberglass batt, frame, and vapor barrier.

In this example, finished Liteblok™ 38 walls are \$7 less per square foot or 37% cheaper than comparably finished traditional 2x6 wood framed walls.

These costs are only an estimate. Costs will vary depending on labor market, project size, application, location, freight rates, and building codes.

Nominal R-value for Liteblok™ 38 is 8 but equivalent, in Austin, TX, to an R-22 wood frame insulated wall as per REScheck energy codes. 2X6 homes insulated with R-19 fiberglass batts have maximum "clear wall" insulation of R-16 but typical "whole wall" insulation of R-14

The costs provided are estimated and are for illustrative purposes only. For exact prices on products supplied by Cresco Concrete Products, LLC, please request a pricelist or quote.

Cresco Concrete Products, LLC Address: 1905 Johanna Drive, Suite B2, Houston, TX 77055
 Toll Free: 1.866.491.6819 Phone: 713.589.5043 Fax: 713.589.9025
 Email: info@crescoconcrete.com Web: www.CrescoConcrete.com